# **INSTALLATION GUIDE**



# 6550-PS Install Track Kit

Promaster, Driver Side



Scan the QR for the latest Install-Guide.






READ, UNDERSTAND, AND FOLLOW ALL WARNINGS AND INSTRUCTIONS BEFORE USING THIS PRODUCT.
FAILURE TO FOLLOW THESE DIRECTIONS MAY RESULT IN PROPERTY DAMAGE, SERIOUS BODILY INJURY,
AND/OR DEATH. RANGER DESIGN IS NOT RESPONSIBLE FOR ANY PROPERTY DAMAGE, PERSONAL INJURY,
OR DEATH THAT OCCURRED WHILE USING ANY RANGER DESIGN PRODUCTS.



- Failure to use Ranger Design-provided fasteners, brackets, and proper installation guidelines could increase risk of serious personal injury and/or death.
- If drilling is required to complete this installation: improper drilling can cause property damage to vehicles and could lead to electric shock, fire, or even death.
- If drilling is required to complete this installation: Ensure that drilling is only performed on areas of the vehicle allowed by the vehicle's Original Equipment Manufacturer's Body Builders Layout Book (or equivalent document).
- Prior to installation, inspect the vehicle to ensure that installation will not interfere with, or cause obstruction of, any critical components such as electrical wiring, fuel tanks, fuel-cells, locks, latches, etc.
- The installer or manufacturer is responsible for ensuring anchorages are installed onto suitable wall and floor structures; wall and floor strength must meet applicable performance requirements.
- Do not install systems into any weak or unsound materials such as plastics, woods, thin-walled metals, etc. without proper reinforcement.
- Do not install this product where it could interfere with the deployment of airbags. Failure to comply could result in death or serious injury.
- Do not install this product where it could ingress on the Transit Occupant Protection Zone. Failure to comply could
  result in death or serious injury.
- Incorrect installation could cause water leaks, electric shock or fire.
- Any cargo vehicle with any cargo or equipment should use a certified partition. See Ranger Design website for some partition options. (https://rangerdesign.com/)
- Mountings rails are recommended for any attachment to the vehicle walls.
- All items in the cargo area should be properly secured and partition doors closed while the vehicle is in motion.
- Check your vehicle's tare weight and remaining load capacity with all the equipment installed. Never exceed the maximum Gross Vehicle Weight Rating (GVWR), Gross Axle Weight Ratings (GAWRs), or other maximum loads permitted by the vehicle's Original Equipment Manufacturer (OEM) and required by law.
- The heaviest items must be placed towards the bottom of the vehicle, while the lightest ones can be arranged upwards. Vehicle cargo loading weight proportion should follow the following guidelines:



- The final alterer and/ or modifier should review the warning sheet with the customer before the vehicle is released to the customer or for general use. These instructions should remain with the vehicles a all times.
- Any modification or unintended use of this product voids any warranty and could create a hazardous condition.
- Ranger Design provides recommended assembly and installation instructions which should be followed to
  ensure correct operation. Failure to do so could result in invalidating the product's compliance, warranty and
  cause injury. Notwithstanding, the final stage vehicle alterer and/or modifier is responsible for the integration,
  installation, and compliance of the product in its final location to all applicable regulations and standards. Failure
  to maintain compliance of the vehicle to applicable regulations and standards could be punishable by law. Alterers and/or modifiers should consult with all local authorities prior to commissioning.



- Drilling is required to complete this installation. Before drilling, ensure that you will not hit any critical parts of the
  vehicle like the gas tank, wiring harness, or hose. Consult the vehicle OEM documentation as necessary. When
  drilling, use a drill collar to reduce the risk of damage to the vehicle.
- Any materials, padding, or glazing installed in the vehicle must comply with FMVSS/CMVSS 201/205/302, as applicable.
- In the event of a motor vehicle accident or collision where a Ranger system has been installed, especially ones
  where the vehicle structure is damaged and/or the air bags deploy and/or the vehicle has been towed, the
  system must be inspected to ensure continued soundness and safety before returning the vehicle to service.
  Damaged components should be replaced as necessary.
- All system components should be regularly inspected, cleaned, and maintained pursuant to Ranger guidelines.

## **QUICK START GUIDE**

## Phase 1 - Assembly

□ 1.1 Setup	4

## Phase 2 - Installation

□ 2.1 Mounting Track Installation	6
□ 2.2 New Shelving Installation w/ Install Track Kit	8

# **REQUIRED ITEMS**

- □ Cordless Impact
  □ Cordless Drill
  □ 1/4" Plusnut Gun or Plusnut Tools
  □ 3/8" Drill Bit
- □ 7/16" Socket
- ☐ 13mm Socket
- □ Tape Measure
- Marker




1 PERSON

# PHASE 1 - ASSEMBLY

## 1.1 SETUP

**1.1.1** Unpack components; compare with the bill of materials.



1.1.2 Verify all parts are present.

### **BILL OF MATERIALS**

Description	Qty.
Mounting Track 40.5"	2
Mounting Track 40"	2
End Cap	8
Customer Fastener Kit	1
	Mounting Track 40.5"  Mounting Track 40"  End Cap

#### 1.1.3 Fastener kits.

## 96-6022 Fastener Kit

## **Fastener Assembly**

12×



# 90-110

Hex Bolt 1/4"-20 × 3/4" **GR-5 ZINC** 

12×



# 94-130

Plusnut .250

12×



# 98-112

Flat Washer 1/4", 3/4" OD ZINC

## 12× FOR PLUSNUT



#90-110 Hex Bolt 1/4" × 3/4"

0 0 #98-118 Lock Washer #98-112 Flat Washer

#94-130 Plus nut

12×



# 98-118

Lock Washer Regular 1/4" ZINC



### FOR SHELVING INSTALL

16×



Channel Nut 5/16"



Hex Bolt 5/16"-18 × 1" **GR-5 ZINC** 

16×



#90-208 Hex Bolt 5/16" × 1"




#94-150 Channel Nut

# PHASE 2 – INSTALLATION 2.1 MOUNTING TARCK INSTALLATION


**1.2.1** Attach one end cap on each side of the mounting tracks.

4×




- **1.2.2** Place the mounting tracks in the van, then mark the holes that need to used to van.
  - Attach plusnut to the van, then install the mounting track.

### **TOP REAR**




## **TOP FRONT**






#### **BOTTOM REAR**



### **BOTTOM FRONT**






## PHASE 2 - INSTALLATION


## 2.2 NEW SHELVING INSTALLATION W/ INSTALL TRACK KIT

**2.2.1** Aligned the wall brackets to the wall mounting track kits, then install the wall brackets to the wall mounting track kits using channel nuts.

**NOTE:** Tightened the bolts that used to attached the wall bracket to the wall or wall kits 1<sup>st</sup> before the bolts that used to attached the wall bracket to the end panel.

**IMPORTANT:** After installation is completed, ensure all bolts are tightened.









# "You have successfully installed your 6550-PS

Thank you for doing business with us."

For any feedback or suggestions you may have, please contact: <a href="mailto:cs@rangerdesign.com">cs@rangerdesign.com</a>



